

BRUHATH BANGALORE MAHANAGARA PALIKE
Ward :14 Bagalagunte


NAME OF WORK :


Construction & Development of 12th Cross Park in Ward No 14 Bagalagunte

Estimated Cost 15.00 Lakhs

Sl	Description of work	Measurments					Qty	Rate	Amount
		Units	No	L	B	D			
1	KSRRB M300-55. Construction of sub-grade and earthen shoulders with approved material Gravel/Murum with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications, including cost of earth, watering charges & compaction by vibratory roller to 97% of modified proctors density) MORTH Specification No. 305 P-147, It-19.62								
		Cum	1	80.00	40.00	0.60	1920.00		
							1920.00	369.94	710285.00
	Basic rate	349.00							
	Area weightage 6%	20.94							
	Total	369.94							
2	KSRRB 300-62. Extra for laying earth by mechanical means as per specifications for compaction in 250mm thick loose layers when laying of earth in layers is done from stacked materials including breaking of clods and dressing but excluding rolling and watering including cost of all labour, HOM complete as per specifications. MORTH / Chapter 3 P-148, IT-19.69, PWD SR 2018-19								
		Cum					1920.00		
							1920.00	61.48	118042.00
	Basic rate	58.00							
	Area weightage 6%	3.48							
	Total	61.48							
3	KSRRB 300-64.1. Extra for watering the earth to bring the earth upto required optimum moisture content manually including cost of all labour complete as per specifications. MORTH / Chapter 3 P-148, It No.19.71, PWD SR 2018-19								
		Cum					1920.00		
							1920.00	12.72	24422.00
	Basic Rate	12.00							
	Area weightage 6%	0.72							
	Total	12.72							
4	KSRRB M400-21. Construction of footpath/separator by providing a 150 mm compacted granular sub-base as per Clause 401 & 25mm thick cement concrete grade M-15, overlaid with precast concrete tiles in cement mortar 1:3 including provision of all drainage arrangements but excluding kerb channel complete as per specifications. MORTH Specification No. 409 P-155, It No.20.21, PWD SR 2018-19								

		Sqm	1	293.00	2.00		586.00		
							586.00	730.34	427979.00
	Basic Rate	689.00							
	Area weightage 6%	41.34							
	Total	730.34							
							Sub Total		1280728
16	Tender Premium Charge 5%								64036.00
18	GST Charge 12%								153687.00
19	Miscellaneous and Unforeseen Charges								1549.00
							Total		1500000.00
	Rupees Fifteen laks only								


Assistant Engineer
Ward No 14


Assistant Executive Engineer
T. Dasarahalli Sub-Division


Executive Engineer
Dasarahalli Division

ಪಂ. EE/DD/AS/110/19-20 ದಿನಾಂಕ :
ರೂ. Rs. 15.00 Laks
Rupees Fifteen Laks only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆದಳತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಓ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ತಾಲೂಕು, ಬೆಂಗಳೂರು

ಪಂ. EE/DD/AS/48/18-19 ದಿನಾಂಕ :
30/01/19
ರೂ. Rs. Fifteen Laks only
(15.00 L.)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆದಳತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಓ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ತಾಲೂಕು, ಬೆಂಗಳೂರು